



बाह्रदशी गाउँपालिका गाउँ कार्यपालिकाको कार्यालय



प.सं. : २०८३/०८४

सू.नं. : ८६



नेपाल सम्बत् १९४६

दरभाउपत्र पेश गर्ने सम्बन्धी सूचना ।

प्रथमपटक प्रकाशन मिति : २०८३/०५/२४

प्रस्तुत विषयमा यस बाह्रदशी गाउँपालिकाको कार्यालयबाट चालु आ. व. २०८३/८४ मा भूमि प्रशासन शाखा व्यवस्थापन गर्नुपर्ने भएको हुँदा यस सूचना साथ संलग्न दररेट फाराम (BoQ) बमोजिमको कार्य तोकिएको समय सिमा अवधि भित्र के कति दर रेटमा सम्पन्न गर्न सक्ने हो ? तपसिल बमोजिमका कागजातहरु सहित यस सूचना प्रकाशनको मितिले ७ दिनको कार्यालय समयभित्र बाह्रदशी गाउँपालिकाको कार्यालयमा खामबन्दी गरी दरभाउपत्र पेश गर्नुहुन यस गाउँपालिकाको मौजुदा सूचीमा सूचीकृत भएका साथै अन्य आधिकारिक फर्म/कम्पनिहरुलाई सूचित गरिन्छ ।

(Handwritten signature)
(गजेन्द्र थपलिया) २०८३/०५/२४

प्रमुख प्रशासकीय अधिकृत

गजेन्द्र थपलिया
प्रमुख प्रशासकीय अधिकृत

तपसिल:

१. फर्म/कम्पनी दर्ताको प्रमाणपत्रको प्रतिलिपि,
२. व्यवसाय दर्ता प्रमाणपत्र/ इजाजतपत्रको प्रतिलिपि (आ. व. २०८३/८४ को लागी नविकरण भएको),
३. मु. अ. कर दर्ता प्रमाणपत्रको प्रतिलिपि,
४. आ. व. २०८२/८३ को करचुक्ता प्रमाणपत्र वा म्याद थपको कागजातको प्रतिलिपि (यस दरभाउपत्रको लागी २०८१/८२ को करचुक्ता भए पुग्ने)
५. रित्तपुर्वक भरिएको साथै फर्मको आधिकारिक प्रतिनिधिमार्फत सहिछाप गरिएको BoQ,
६. यस कार्यालयमा सूचीकृत भएका फर्महरुको हकमा सूचीकृत दस्तुर तिरेको रसिदको प्रतिलिपि र सूचीकृत नभएकाहरुको हकमा रु १,०००।०० (फिर्ता नहुने) यस कार्यालयको राजस्व शाखामा जम्मा गरी सोको सक्कल भौचर र माथि उल्लेखित १ देखि ४ सम्मका कागजातहरु संलग्न राखी सूचीकृतको निवेदन दर्ता गरी सो दर्ता भएको निवेदनको प्रतिलिपि र सूचीकृत दस्तुरको भौचरको प्रतिलिपि (थप २ कागजात) पेश गर्नु पर्नेछ ।

(Handwritten signature)
२०८३/०५/२४



गाउँ कार्यपालिकाको कार्यालय, चकचकी, झापा, कोशी प्रदेश, नेपाल

कार्यालय कोड नं.: ८०१०११२१३

म.लै.प.फारम नं:
५०१२५०१ (क) एकिकृत

कार्यक्रम / योजनाको नाम : भूमि प्रशासन शाखा व्यवस्थापन
कार्यक्रम / योजनाको कार्याव्ययन हुने स्थल: बाह्रदशी गाउँपालिका
सम्पन्न हुने अनुमानित अवधि:.....

आर्थिक वर्ष: २०८३/८४
बजेट उप शीर्षक नः
खर्च हुने बजेट: ९१५६२६.१५
जनसहभागिता:

Bill of Quantities (BoQ)

क्र.सं.	काम/सेवाको विवरण		एकाइ	परिमाण	दर	जम्मा लागत	अनुमानित दरको स्रोत
	आइटम						
१	२		३	८	९	१०=८x९	११
1	Notice board(flex type)		ls	1.00			
2	Earthwork in Excavation in soft soil manually upto depth of 1.5m and hauling distance of at least 10m including dressing of the sides and proper compaction all works complete as per the instruction of the engineer		Cum.	1.70			
3	Concreting (1:3:6) of foundation vertical faces,walls(cement concrete) including supply of materials and haulage distance up to 30m By mechanical means.		Cum.	4.62			
4	38 mm thick cement concreting works including punning all complete in 1:2:4 ratio		Sqm.	30.78			
5	Providing and laying of Plain Cement Concrete M15 (or 1:2:4 for nominal mix) complete as per Drawing and Technical Specifications.[2000]		cum	0.85			

7809

3. BoQ इन्जिनियर (आडों)

Page 1 of 4

जमका - सहित :

क्र.सं.	कामसेवाको विवरण		एकाइ	परिमाण	दर	जम्मा लागत	अनुमानित दरको स्रोत
	आइटम						
6	Providing , Preparing and Installing form work including necessary supports and removing after completion for foundation and footings. (Class F1 Finish) Using timber (soft wood) [1804, 1805] (assuming 2 times usage)		Sqm.	2.57			
7	Aluminium Framed Fixed Partition with Naturally Anodized Colour in the Section of 101 x 45 x 1.5 mm including 5 mm thick Glass or Board 9mm Laminated		Sqm.	18.14			
8	Aluminium Framed Anodized Colour in the Section of 101 x 45 x 1.5 mm (6m=3.5Kg)		kgs.	3.33			
9	Aluminium Framed Casement door one way openable with Naturally Anodized Colour in the Section of 101x45 x1.5 mm including 5 mm thick Glass		Sqm.	6.33			
10	Aluminium Framed Sliding Door with Naturally anodized Colour in the Section of 101 x 45 x 1.5 mm with 5 mm thick Glass.		Sqm.	1.85			
11	Aluminium Framed Sliding window without Ventilater and Flymesh at sliding Windows with materials in the section of 88x38 x1.30 mm in Naturally Anodized Colour including 5 mm thick Glass		Sqm.	1.70			
12	Fixing 5 mm thick Glass in old aluminium partition with all fitting and complete works.		Sqm.	4.41			
13	Supplying and fitting iron tubular truss including prime coat, welding, placing as per drawing and specification all complete		kgs.	791.02			
14	26 gauge medium colour CGI sheet roofing works with supply of materials all complete (0.36mm thick, 57kg/bundle weight)		sqm.	154.15			
15	Making and fixing 4mm thick glazed shutter using sal wood shutter of size 38*75mm.		Sqm.	1.83			



प्रमुख प्रशासकीय अधिकारी
पृष्ठ 2 of 4

नारायण प्रसाद खरेल
3. BoQ इन्जिनियर (आर्क)

जर्ज खरेल

क्र.सं.	काम/सेवाको विवरण		एकाइ	परिमाण	दर	जम्मा लागत	अनुमानित दरको स्रोत
	आइटम						
16	Making & fixing 4mm thick glass using necessary listi.		Sqm.	2.75			
17	Making and fixing of seasoned sal wood pannelled shutter using 38*75mm sal wood frame		Sqm.	3.17			
18	M.S. grill works in plain design & approved pattern manufactured finished with one coat of red lead primer paints as per specification and instruction of site Engineer.(1sqm=17kg)		Sqm.	2.68			
19	26 gauge medium colour CGI Plain sheet roofing works with supply of materials all complete.		Sqm.	10.34			
20	cutting,weilding and prime coating of chain gate(5*50mm size and 50mm gap including fitting all complete(1sqm=30kg)		kgs.	291.60			
21	Single coat Exterior plastic emulsion paint with one coat primer		sqm.	184.05			
22	Double coat Interior plastic emulsion paint with one coat primer		Sqm.	176.08			
23	Two coat Readymade Enamel paint without primer for iron works		sqm	71.70			
क. जम्मा रकम							
ख. मु.अ.कर (क को १३%)							
ग. कुल जम्मा (क+ख)							

तयार गर्ने:.....

नाम:

१८०१

जाँच गर्ने:.....
नाम: *[Signature]*

आस्थापना प्रमुख खरेल
3. BOD निर्वाहक (आ.स.)



स्वीकृत गर्ने:.....
नाम: *[Signature]*

प्रमुख प्रशासकीय अधिकारी
प्रमुख प्रशासकीय अधिकारी

०१/०३/२०७५